



- Adhered Drystack thin stone veneer units (ASTM-C1670 Compliant)
- Min. 6.4 mm THK. setting bed mortar (Laticrete Hi-Bond Masonry veneer mortar, Specmix XP 500 or Custom Building Products Flexbond)
- Min. 16 mm Exterior Grade Cement board (Permabase or equivalent) c/w manf. recommended fasteners) and spacing by other
- 16 ga. vertical Thermally broken z-bars - 13 mm deeper than insulation @ 406 (16") o.c
- 13 mm airspace
- Insulation between z-bars
- Weather Resistant Barrier (WRB)
- 16 mm exterior grade sheathing
- 152 mm 16 ga. steel studs at 16" o.c.
- R22 Batt insulation
- 6 mil Poly vapour barrier
- 13 mm Interior Gypsum

51 mm x 50 mm x 16ga. metal angle support fastened @ 406 mm (16") o.c.

Thru wall flashing